

Beaufort County Public Works

Stormwater Infrastructure Project Summary

Project Summary: Grande Oaks Drive

Narrative Description of Project:

Project improved 2,201 L.F. of drainage system. Cleaned out 2,001 L.F. of roadside ditch. Cleaned out (1) catch basin. Jetted (2) crossline pipes, (17) driveway pipes and 200 L.F. roadside pipe. Hydroseeded for erosion control.

2011-620 / Grande Oaks Drive	Labor	Labor	Equipment	Material	Contractor	Indirect	
	Hours	Cost	Cost	Cost	Cost	Labor	Total Cost
AUDIT / Audit Project	1.00	\$20.48	\$0.00	\$0.00	\$0.00	\$0.00	\$20.48
CBCO / Catch basin - clean out	8.00	\$171.32	\$88.64	\$53.86	\$0.00	\$0.00	\$313.82
CLPJT / Crossline Pipe - Jetted	14.00	\$299.81	\$155.12	\$53.39	\$0.00	\$0.00	\$508.32
COMP / Compile Project	1.00	\$20.48	\$0.00	\$0.00	\$0.00	\$0.00	\$20.48
DLO / Ditch Layout	20.00	\$445.70	\$153.70	\$67.15	\$0.00	\$0.00	\$666.55
DPJT / Driveway Pipe - Jetted	12.00	\$256.98	\$132.96	\$49.90	\$0.00	\$0.00	\$439.84
HAUL / Hauling	55.00	\$1,178.10	\$732.05	\$369.24	\$0.00	\$0.00	\$2,279.39
HYDR / Hydroseeding	15.00	\$338.60	\$51.70	\$256.90	\$0.00	\$0.00	\$647.20
PTS / Portable Toilet Service	0.00	\$0.00	\$0.00	\$0.00	\$109.75	\$0.00	\$109.75
RSDCL / Roadside Ditch - Cleanout	136.00	\$3,031.69	\$737.26	\$234.21	\$0.00	\$0.00	\$4,003.16
UTLOC / Utility locates	2.50	\$51.20	\$10.30	\$10.35	\$0.00	\$0.00	\$71.85
Indirect Labor, Services and Supplies	0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$3,954.91	\$3,954.91
2011-620 / Grande Oaks Drive	264.50	\$5,814.36	\$2,061.73	\$1,095.00	\$109.75	\$3,954.91	\$13,035.75
Sub Total							
Grand Total	264.50	\$5,814.36	\$2,061.73	\$1,095.00	\$109.75	\$3,954.91	\$13,035.75

Before





Completion: May-11



